



CASE STUDY

West Hendon Redevelopment

THE PROJECT

Regeneration project in Hendon to build 2,000 new mixed tenure homes to grow a thriving and cohesive neighborhood.

THE PROBLEM

The size of the project made designing the piles and retaining wall challenging.

REMEDY'S SOLUTION

Design of contiguous bored pile retaining walls, bearing piles and technical advice on temporary ground anchors.

TESTIMONIAL

"Remedy quickly got a grip of the technical challenges of this project and assisted us in getting this complex development out of the ground as fast as possible."

Mike Bardy, Technical Manager,
Barratt London

Leave the ground to us!

www.remedygeotechnics.com

Follow Us @RemGeotechnics

Basement Retaining Walls, Bearing Piles & Ground Anchors

Remedy were able to bring their basement and pile design expertise to bear on this flagship development undertaken by Barnet Council, by Barratt London. The challenge was to design and schedule over 400 linear meters of contiguous bored pile retaining wall and 640 bearing piles to facilitate fast track installation by specialist contractor Hill Piling Ltd. Significant economy in the piling was achieved by optimizing the designed pile length following analysis of a 3 cycle load test on a 36m long 600mm diameter preliminary test pile.

Remedy designed the one and two storey basement retaining walls (formed from 750mm, 600mm and 450mm diameter piles) to the latest Eurocode standards. Remedy had to ensure the retaining wall was designed to enable the substantial building loads to be carried in the permanent condition.

Remedy were able to address, very effectively, the challenges commonly found where deep basements are constructed in a congested urban environment. These included consideration of potential ground movements

affecting sensitive party walls, and designing a large span of retained height adjacent to a car ramp.

When the ground worker in charge of excavation of the two storey basement proposed substituting temporary ground anchors in place of the originally specified internal steel propping, Remedy were engaged directly by Barratt London to act as their specialist anchor advisor. As it turned out, both the piling contractor and their client were able to leave the ground to us!

Contact Remedy Geotechnics - we'll give you an answer every time.

London & Midlands

0207 206 2576
01788 211778

North & Scotland

01423 589500